

Item Number (upto 200 characters)	Item Description	Quantity (only figures)	UNIT (upto 50 characters)	Tender Rate (Upto 2 Decimals)	Amount (Upto 2 Decimals)
1	Excavation for foundation up to 1.5 mt. depth including sorting out and stacking off useful materials and disposing off the excavated stuff up to 50 mt. lead. (A) loose or soft soil	6.00	C.M.	123.13	738.78
2	Excavation for foundation for depth from 1.5 mt. to 3.0 mt, depth including sorting out and stacking off useful materials and disposing off the excavated stuff up to 50 mt. lead. (A) loose or soft soil	6.00	C.M.	136.47	818.82
3	Boring holes 3.5 mt. deep in ordinary soil (for cast in situ piles) & disposal of the surplus excavated soil as directed within a lead of 50 m. For following diameter of piles. (2) For 250 mm dia.	2.00	Each	1335.62	2671.24
4	Providing & Laying cement concrete 1 : 3 : 6 (1 cement : 3 coarse sand : 6 hand broken stone aggregate 40 mm nominal size) and curing complete excluding cost of formwork in : (A) Foundation and Plinth	1.00	C.M.	3095.25	3095.25
5	Providing & Laying controlled cement concrete M.200 and curing complete including the cost formwork and excluding cost of reinforcement for reinforced concrete work in (A) Foundation, footing, base of columns and mass concrete	1.00	C.M.	4728.82	4728.82
6	Providing & Laying controlled cement concrete M.200 and curing complete including the cost formwork and excluding cost of reinforcement for reinforced concrete work in (A) Column	2.00	C.M.	9163.73	18327.46
7	(B) Beam	2.00	C.M.	7283.11	14566.22
8	Providing TMT IS MARK BAR FE 500/500D steel reinforcement for R.C.C. work including binding, binding and placing in position etc. comp.	850.00	Kg.	77.29	65696.50
9	Filling available excavated earth (exluding rock in trenches plinth, Sides of foundations etc. in layers not excluding 20 cm in depth consolidating each diposited layer by raming and watering.	8.00	C.M.	136.92	1095.36
10	Brick work using common burnt clay building brick having crushing strength not less than 35 kg/sq. cm. in foundation plinth in cement mortar 1 : 6 (1 cement : 6 fine sand) (A) Conventional up to floor two lvl.	4.00	C.M.	4503.04	18012.16
11	20mm thick sand faced cement plaster on wall upto height 10 meters above ground level consisting of 12mm. thick backing coat of c.m. 1:3 (1 cement : 3 sand) and 8mm. thick finishing coat of c.m. 1:1 (1 cement : 1 sand) etc. comp.	32.00	S.M.	347.42	11117.44
12	Steel work welded in built up sections, framed work including cutting, hoisting, fixing in position and applying a priming coat of red lead paint. (A) In beams & joists channels angles, tees, flats with connection plates or angle cleats as in main & cross beams, hip & trussed purlins connected to common raffers & the like	450.00	Kg.	91.08	40986.00
13	Painting two coats (excluding priming coat) on new steel and other metal surface with synthetic enamel paint. brushing to give an even shade including cleaning the surface of all dirt, dust and other foreing matters.	34.00	Kg.	92.20	3134.80
14	Prividing & applying Texture Paint to give an required shape even shade after thoroughly brushing the surface to remove all dirt, and remain of loose powdered material etc. complete.	34.00	S.M.	543.38	18474.92
	TOTAL AMOUNT				203463.77